Abstract Notification, dated 17th February 1936.

The attention of the public is invited to the notification on pages 257-258, Part VI of the *Mysore Gazette*, dated 20th February 1936, inviting tenders for the work of improvements to the feeder channel of Bodimarlur tank Register No. 164, Goribidnur Taluk.

The last date for the receipt of tender is 2 P.M. on the 16th March 1936.

Notification, dated 14th February 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 16th March 1936, for filling in the breach and extending the weirs at both flanks of Maddepalli Doddakere Register No. 860, Bagepalli Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. to 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 1,000 (One thousand only) in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for filling in the breach and extending the weirs at both flanks of Maddepalli Doddakere Register No. 860, Bagepalli Taluk" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for filling in the breach of Maddepalli Doddakere Register No. 860, Bagepalli Taluk and extending the weirs at both the flanks.

No.	Items of work	Unit	Rate	Quantity	Cost
	I. Breach filling at Centre (grades 7—10).		Rs. a. p.		Rs.
1	Clearing site and jungle and removing debris and boulders and baling water at site of breach ..	L. S.	..	..	150
2	Removing silt and slush in the breach not proposed to be used for the bund	C.yd.	0 3 0	3,467	..
3	Bending rock for seat of core wall	S.ft.	0 8 0	564	..
4	Size stone in surki mortar	C.ft.	0 5 0	2,180	..
5	Providing puddle wall	C.yd.	0 12 0	842	..
6	Providing jelly drain behind core wall ..	C.yd.	1 0 0	116	..
7	Cutting steps and grips in the sides of the breach and using the same for the rear of the bund with watering and consolidation..	C.yd.	0 5 0	519	..

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
8	Roughening the surface of rock for the seat of earth	L. S.	..	..	50
9	Cutting grips and bund of high level breach and using the same for bund with watering and consolidation	C.yd.	0 5 0	143	..
10	Earthwork filling in the breach with mixture of 50 per cent clay and gravel (with lead of ½ mile for gravel and left)	C.yd.	0 8 0	16,424	..
11	Gravel backing behind revetment 1 foot thick ..	C.yd.	0 12 0	510	
12	Rough stone work new	,,	1 8 0	1,264	
13	Removing the washed out stones of old revetment and reconstructing the same with new jelly	,,	1 0 0	125	
14	Turfing the slopes of bund	S.yd.	0 1 0	2,596	
15	*Filling in the scour between grades* 14 *and* 15 *in the rear.*				
	(*a*) Filling in the scour with good gravel and clay in equal proportions of 50 per cent (with lead for gravel half mile) including watering and consolidation	C.yd.	0 8 0	676	
	(*b*) Turfing the rear slope	S.yd.	0 1 0	245	
	(*c*) Rough stone work new	C.yd.	1 8 0	35	
16	Compensation for acquisition of lands for excavation of gravel	acres	50 0 0	4	
17	Sinking a well in the tank bed for earthwork consolidation	L. S.	..	..	300
	II. Repairs to the existing Left Waste Weir 65 *ft. long and extending the same by* 75 *ft. (Total* 140 *ft.) with crest at R. L.* 50·00.				
1	Clearing site and cutting bund for return of weir.	L. S.	..	..	25
2	Excavating foundations in disintegrated soft rock for body wall	C.yd.	0 10 0	47	
3	Concrete in surki mortar	C.ft.	0 4 3	638	
4	Size stone in surki mortar	C.ft.	0 5 0	1,866	
5	Pointing with cement mortar	Sqr.	4 0 0	8.18	
6	Burnt stone slabs 6″ thick dressed and fixed ..	S.ft.	0 5 0	149	
7	Providing joggle joints	Each	0 12 0	12	
8	Repairs to existing brick masonry, including plastering, etc.	L. S.	..	..	10
9	Removing and refixing coping slabs including cement pointing	S.ft.	0 2 0	113	
10	Rough stone work new	C.yd.	1 8 0	395	
11	Big boulders filling beyond toe wall with available stones closeby	C.yd.	0 12 0	260	
	III. Repairs to the existing Right flank weir 100 *feet long and extending the same by* 51 *feet with crest at* 50·00. (*Total including return of* 9 *feet* 160′—0″.)				
1	Clearing site and dismantling the returns and steps	L. S.	..	..	25
2	Benching rock for the extension of body wall and returns	S.ft.	0 8 0	344	
3	Size stone in surki mortar	C.ft.	0 5 0	1,283	
4	Burnt stone slabs 6″ thick dressed and fixed ..	S.ft.	0 5 0	132	
5	Providing joggle joints	Each	0 12 0	6	
6	Pointing with cement mortar	Sqr.	4 0 0	7.84	
7	Resetting the displaced coping slabs in surki mortar including cement pointing ..	S.ft.	0 2 0	90	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
8	Rough stone work for wings using the stones available from blasting the approach ..	C.yd.	0 8 0	21	
9	Clearing approaches by blasting boulders to F.T.L.	Cyd.	1 8 0	45	
10	Blasting the sheet rock in the draft side ..	C.yd.	2 8 0	15	..
11	Sundry repairs to sluice and providing plug and rod with locking arrangements ..	L. S.	..	..	50
	IV. Repairs to low level sluice.				
1	Removing and reconstructing old revetment with new jelly	C.yd.	1 8 0	18	..
2	Cutting open the bund and refilling with watering and consolidation	C.yd.	0 6 0	311	..
3	Examining and repairing the sluice	L. S.	..	..	50
4	Providing plug and rod with locking arrangements	,,	..	..	15
	V. Miscellaneous.				
1	Constructing a temporary shed for the subordinate	L. S.	..	..	100

Notification, dated 14th February 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 16th March 1936, for restoring Mutakapalli Doddakere, Register No. 788, Bagepalli Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees four hundred only (Rs. 400) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Mutakapalli Doddakere, Register No. 788, Bagepalli Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for restoring Mutakapally Doddakere, Register No. 788, Bagepalli Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
	I. *Bund R. L. 55.00 Top width 4½ ft. slopes 1½ to 1 and 2 to 1.*				
1	Clearing jungle with removal of roots, etc. ..	Grade	1 8 0	17	
2	Cutting grips and trenches for the seat of new earth	,,	2 0 0	17	
3	Removing ant-hills and filling them with good gravel and sand consolidating	Each	1 0 0	15	
4	Removing top soil and loose earth at the scoured portions of bund	Grade	15 0 0	4	
5	Earthwork to bund with select earth watering and consolidating	C.yd.	0 4 0	8,785	
5(*a*)	Extra rate for lead, watering and consolidating earth got from waste weir	C.yd.	0 2 6	640	
6	Turfing the slopes of bund	Sq. yd.	0 0 9	5,588	
7	Removing and resetting old stone revetment with new jelly wherever necessary ..	L. S.	..	..	50
8	New stone revetment	C.yd.	1 8 0	348	
9	Providing and fixing new grade stones with cutting figures, painting, etc., complete. ..	Each	1 12 0	18	
10	Do Index stones do ..	,,	0 8 0	18	
11	Do Register No. and date stone do	,,	3 0 0	1	
12	Do B. M. Stones do ..	,,	2 8 0	2	
13	Do Gauge stone do ..	,,	15 0 0	1	
	II. Breach filling.				
1	Clearing site of breach and bailing water ..	L. S.	..	..	25
2	Clearing silt and sand at site	C.yd.	0 3 0	1,118	
3	Earthwork excavating foundations for the seat of new earth and using the same for rear slope	C.yd.	0 3 0	439	
4	Clay puddle for core wall	,,	0 10 0	338	
5	Earthwork filling in breaches with select earth (50 per cent clay and 50 per cent gravel) watering and consolidating with lead and lift	,,	0 6 0	3,653	
5(*a*)	Extra rate for lead, watering and consolidating earth got from foundations	,,	0 2 6	351	
6	Gravel backing to revetment 9″ thick ..	,,	0 8 0	89	
7	New stone revetment	,,	1 8 0	308	
8	Turfing the slopes	Sq.yd.	0 0 9	587	
	III. Sluice.				
	Repairs to the existing masonry sluice, providing plug and rod with locking arrangement, etc., complete	L. S.	..	....	100
	IV. Extending the existing Waste Weir 110 ft. long by 190 ft. total length will be 110+190= 390 ft. with crest at R. L. 50·00.				
1	Earthwork excavating for draft and approaches and using the earth for bund	C.yd.	0 3 0	800	
2	Burnt stone jelly concrete in surki mortar ..	C.ft.	0 4 0	599	
3	Burnt size stone in surki mortar	,,	0 5 0	964	
4	Burnt stone slabs 6 inches thick, dressed and fixed	Sq.ft.	0 5 0	1,071	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
5	Pointing with cement mortar	Sqr.	4 0 0	12·78	
6	Removing old stone revetment of the right training bank and using the same for apron with new jelly	C.yd.	0 8 0	31	
7	Rough stone work for apron	C.yd.	1 8 0	107	
8	Removing and resetting old stone apron wherever necessary with new jelly	L. S.	..	..	30
9	Repairs to the existing weir	,,	..	..	30
10	New joggle joints 8 ft. c to c	Each	1 0 0	24	

Notice, dated 14th February 1936.

Notice is hereby given that sealed tenders will be received upto 2 P.M. of 9th March 1936, at the Office of the Executive Engineer, Kolar Division, Kolar, for running a Coffee Club in the premises of District Office Buildings, Kolar, for a period of one year from 15th March 1936 or immediately thereafter as soon as the tender is accepted.

2. Tenders should be accompanied by an earnest money of Rs. 10 only (Rupees Ten only) in cash and should be presented "tender for running a Coffee Club House, in the premises of Kolar District Office Buildings".

3. The monthly rate of rent offered in the tender must be written both in words and in figures.

4. The acceptance of tender rests with the Executive Engineer, Kolar Division, who will have the power to reject or accept any tender without assigning any reason. His decision will be final and binding on all tenders.

5. The earnest money of the unsuccessful tenderers will be refunded.

6. The monthly rate of rent offered should be paid in advance before the 5th of each month.

Notification, dated 14th February 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 16th March 1936, for restoring Bagepalli Voddu Register No. 639, Bagepalli Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees three hundred and seventy-five only (Rs. 375) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Bagepalli Voddu, Register No. 639, Bagepalli Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for restoring, Bagepalli Voddu, Register No. 639, Bagepalli Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
	I. Bund R. L. 56.00 Top width 6'—0" Side slopes 1½ : 1 & 2 : 1.				
1	Clearing jungle and removing ant-hills ..	Grade	2 0 0	14	
2	Cutting grips and trenches to bund	,,	1 8 0	14	
3	Earthwork to bund with watering and consolidation	,,	0 3 6	1,809	
4	Lead and watering charges and consolidation for the earth got from approach clearing ..	C.yd.	0 1 0	1,303	
5	Turfing the slopes of bund	Sq. yd.	0 0 9	3,103	
6	New stone revetment	C.yd.	1 8 0	99	
7	Removing and resetting old stone work with new jelly	,,	0 8 0	100	
8	*Tracing the leak and closing the same.*				
	(*a*) Cutting open bund	,,	0 3 0	117	
	(*b*) Filling with 50 per cent clay and gravel including watering and consolidation ..	,,	0 6 0	117	
9	Removing and refixing old grade stones including figuring and painting, etc., complete ..	Each	0 8 0	8	
10	Providing and fixing new grade stones, including figuring and painting, etc., complete ..	,,	1 8 0	6	
11	Removing and refixing old index stones, including figuring and painting, etc., complete ..	,,	0 4 0	4	
12	Providing New index stones do ..	,,	0 6 0	10	
13	Providing and fixing Register No. and date stones do do ..	,,	3 0 0	1	
14	Do do B. M. stones do	,,	2 8 0	2	
15	Removing and refixing old gauge stone including figuring and painting, etc., complete ..	,,	5 0 0	1	
	II. Breach filling.				
1	Clearing site and debris and baling water and removing roots	L. S.	..	..	75
2	Cutting grooves at ends of old bund and cutting grips and using the same to rear bund, including consolidation	C.yd.	0 3 0	349	
3	Clearing silt in the breach portion	,,	0 3 0	1,778	
4	Cutting grips for seat of bund	C.yd.	0 3 0	105	
5	Earthwork excavating foundation for puddle wall	,,	0 3 0	87	
6	Providing puddle clay for core wall	,,	0 10 0	469	
7	Providing jelly drain	,,	1 0 0	52	
8	Earthwork to breach with 50 per cent clay and gravel, with watering and consolidation ..	,,	0 6 0	5,170	
9	Turfing the slopes of bund	Sq. yd.	0 0 9	880	
10	Gravel backing behind revetment	C.yd.	0 8 0	285	
11	Rough stone work new	,,	1 8 0	635	
	III. Sluice.				
1	Sundry repairs to existing masonry	L. S.	..	..	10
2	Providing and fixing plug and rod with locking arrangements	L. S.	..	..	15
	IV. Extending the existing left Waste Weir 33 feet long by 160 feet towards left (total length 193 feet) with Crest R. L. 50.00.				
1	Approach earthwork clearing and using the same to rear of bund	C.yd.	0 3 0	1,303	
2	Earthwork excavating foundations ..	,,	0 3 0	286	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
3	Burnt stone jelly concrete in surki mortar ..	C.ft.	0 4 3	504	
4	Size stone in surki mortar	,,	0 5 0	638	
5	Burnt stone slabs 6" thick, neatly dresseda nd fixed	Sq.ft.	0 5 0	787	
6	Joggle joints	Each	0 8 0	25	
7	Rough stone work new for apron	C.yd.	1 12 0	111	
8	Pointing with cement mortar	Sqr.	4 8 0	8.90	
9	Dismantling old masonry	C.ft.	0 0 6	80	
10	Removing and refixing coping slabs in surki mortar	S.ft.	0 2 0	50	
11	Removing and resetting old apron with new jelly	L. S.	..	..	20
	Right Waste Weir.				
1	Removing and refixing coping slabs in surki mortar	Sq.ft.	0 2 0	45	
2	Sundry repairs to left return	L. S.	..	..	10
3	New rough stone apron in place of damaged ones	C.yd.	1 12 0	218	
4	Removing and resetting old stone revetment with new jelly	,,	0 8 0	10	
	VI. *Compensation for 4 acres of land to be acquired for the extension of the Weir* ..	L. S.	..	..	300

Notification, dated 14th February 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 16th March 1936, for constructing a New Masonry Weir at the right end, in place of the damaged weir and closing the breach of Thimmapalli Kaniveekere, Register No. 858, Bagepalli Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed :—

4. Each tender must be accompanied by a deposit of Rs. 350 (Three hundred and fifty only) in cash or Government Promissory Notes as earnest money, and be superscribed " Tender for constructing a new masonry weir at the right end in place of damaged weir and closing the breach of Thimmapalli Kaniveekere, Register No. 858, Bagepalli Taluk " in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond ; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for constructing a new weir at the right end in the place of damaged weir and closing the breach of Thimmapalli Kanivekere Register No. 858, Bagepalli Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
	I. Constructing a new masonry weir 110 *feet long at right flank in place of breached weir of* 89 *feet long at* 50.00.				
1	Clearing site and removing boulders sand, etc.	L. S.	..	..	20
2	Cutting high ground in hard gravelly soil ..	C.yd.	0 4 0	65	16
3	Excavating and benching in soft and hard rock for the foundation of body wall	C.yd.	2 0 0	190	380
4	Stone jelly concrete in surki mortar	C.ft.	0 4 3	2,323	617
5	Burnt size stone in surki mortar mass work with full stones dressed	,,	0 4 6	12,531	3,525
6	Burnt stone slabs 6" thick dressed and fixed ..	S.ft.	0 5 0	476	149
7	Pointing with cement mortar	Sqr.	4 0 0	408	179
8	Providing joggle joints 8' apart	Each	0 12 0	26	20
9	Rough stone flooring with heavy boulders with surki mortar	C.ft.	0 3 6	1,703	373
10(*a*)	Rough stone work for apron	C.yd.	0 12 0	170	255
b)	Concrete grouting for a apron	C.ft.	0 4 6	401	113
11	Draft and approach clearing in hard gravelly soil and using the same for bund with consolidation	C.yd.	0 6 0	393	147
12	Earthwork for connecting old bund with consolidation	C.yd.	0 6 0	40	15
	Total ..				5,809
	II. Protecting Scour in front at approaches.				
(*a*)	Earthwork for filling in scour with consolidation	C.yd.	0 6 0	208	78
(*b*)	Rough stone work	,,	1 8 0	341	511
(*c*)	Filling in front of body wall with puddle and consolidating the same	,,	0 8 0	80	40
	Total ..				629

Notification dated 14*th February* 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 16th March 1936, for restoring Balareddipalli Gurrammanakere, Register No. 635, Bagepalli Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

4. Each tender must be accompanied by a deposit of Rs. 300 (Three hundred only) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Balareddipalli Gurrammanakere, Register No. 635, Bagepalli Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond ; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for restoring Balareddipalli Gurrammankere Register No. 635, Bagepalli Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
	I Bund at R. L. 56.50. *Top width* 6' *Slopes* 1½' *to* 1 & 2 *to* 1.				
1	Clearing jungle with removal of root, etc. ..	Grade	1 0 0		8
2	Cutting grips and grip trenches for receipt of new earth	,,	1 0 0		8
3	Removing ant-hills and filling them with good gravel and sand consolidating	Each	1 0 0		5
4	Earthwork to bund with watering and consolidating	C.yd	0 4 0		616
5	Turfing the slopes of bund	Sq.yd.	0 0 9	1,197	
6	Removing and resetting old stone revetment with new jelly	C.yd.	0 8 0		20
7	New stone revetment	,,	1 8 0		38
8	Removing and refixing old grade stones cutting figures, painting, etc., complete	Each	0 8 0		9
9	Do Index stones do	,,	0 2 0		9
10	Do Register No. and date stone complete	,,	0 8 0		1
11	Do Gauge stone do	,,	3 0 0		1
	II. Sluice.				
1	Sundry repairs	L. S.	..	..	5
2	Providing plug and rod with locking arrangements, etc., complete	L. S.	..	..	15
	III. Left waste weir at R. L. 50.00 *length* 80*ft.*				
1	Clearing site of loose boulders and debris and providing ring bund, etc.	L. S.	..	..	50
2	Dismantling existing body wall	C.ft.	0 0 6	2,428	
3	Blasting and benching in hard rock to an average depth of 3' for the seat of body wall	C.yd.	3 0 0	110	
4	Burnt size stone in Surki mortar	C.ft.	0 4 6	8,290	
5	Burnt stone slabs 6" thick dressed and fixed ..	S.ft.	0 5 0	352	
6	Providing joggle joints 8ft. C. to C.	Each	1 0 0	20	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
7	Cement mortar pointing	Sqr.	4 0 0	25·19	
8	Cement mortar for masonry foundations ..	L. S.			50
9	Graded rough stone in surki mortar for filling in pouches in sheet rock	C.ft.	0 3 0	5,490	
10	Stone jelly concrete in surki mortar for foundation crevices	,,	0 4 0	192	
11	Earthwork to bund with watering and consolidating, etc.	C.yd.	0 4 0	223	
12	Removing and resetting old stone revetment with new jelly	,,	0 8 0	33	
	IV. Constructing a cushion wall lower down the weir.				
1	Blasting and benching in hard rock for the foundations of cushion wall	C.yd.	3 0 0	21	
2	Burnt size stone in surki mortar	C.ft.	0 4 6	1,140	
3	Burnt stone slabs 6″ thick dressed and fixed in surki mortar	S.ft.	0 5 0	140	
4	Cement mortar pointing	Sqr.	4 0 0	7.4	
5	Providing joggle joints 8ft. C. to C.	Each	1 0 0	10	
6	Graded rough stone in surki mortar for filling in pouches	C.ft.	0 3 0	540	

N. SUBBA RAO,
Executive Engineer.

SHIMOGA DIVISION.

Notification dated 16th February 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 2 P.M., on Monday the 16th March 1936 for renovating the old Jail Building at Shimoga. An approximate estimate of quantities is given overleaf. These quantities are not guaranteed. The work should be completed by the end of December 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given overleaf, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a Treasury Chellan for having deposited a sum of Rs. 300 (Three hundred only) as earnest money, and be superscribed " Tender for renovating the old Jail Building at Shimoga" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will b required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.